



# Weymouth Golf Club

## 2021 – 2026 Five year plan [OIC Rob Mabb]



Area	Tees	Fairways & Approaches	Bunkers	Greens	Irrigation & Drinking water	Drainage	Paths & Steps	Hedges & Scrub Areas	Tree Management
Lead Green Keeper	Jimmy Hallett	Ben Tyrrell	Sam Trott	Rob Mabb	Jimmy Hallett Ben Tyrrell Sam Trott	Rob Mabb	Jimmy Hallett	Mark Venner	Mark Venner
<b>2021/22</b>  <b>Review Dates</b> <b>Sept 2021</b> <b>Dec 2021</b>	Re shape earthworks in front of 8th Tee for winter tee mat - September/ October  Replace rotten sleeper edges and steps on 1st, 5th, and 9th winter tees - Over winter	Mole Plough. Aeration. Raise and level sunken drains and holes - Over autumn/early winter	Commence work on reshaping the greenside bunkers as per the Bunker development plan. 8th Green - September/ October.	Look into a better system of laying and collecting tarpaulins for leather jackets - Over winter.	Replace hardware valves taps etc in green control boxes on four holes. Raise and level green and approach sprinkler on 9 holes. Re-route Irrigation pipes on 4th tee - Over winter.	Install drain above 6th green to stop surface water flooding of green - Late October.  Obtain prices for drainage at 13th approach.	Fit new Grippers to sleeper steps on 2 holes - Jan 2022.  Complete Stone Buggy paths at 2 and 3 - September 2021.	Cut back vegetation along public foot path to enable machinery access for ditch cleaning operations - January/February 2022.  Thin back hedge in front of ladies 17th tee	Start work on the tree development plan and prices. Fell selected Leylandii trees at the 8th (Contractor). Remove lower branches that may impede buggies Over Winter. Grind down remove and make good tree stumps about course Over Winter - Late September early October. Remove Poplars at 9 and 18 to stop root ingress in bunkers - February/March 2022.
<b>2022/23</b>  <b>Review Dates</b> <b>Mar 2022</b> <b>June 2022</b> <b>Sept 2022</b> <b>Dec 2022</b>	Replace sleeper edges to winter tee mats and tee at 4th and 2nd	Mole Plough. Aeration. Raise and level sunken drains and holes. Shape area to the right of the 6th fairway.	Continue work on Greenside Bunkers as per development plan. (Min of two bunkers) Focus on the 2nd & 10th, along with removal of fairway bunker on 17th.	Relay and adjust levels to shed surface water on new chip/putting green.	Water pipe to drinking fountain at 5, to be diverted away from the front of 4th green or re-laid deeper. Continue green control box renewal on 4 holes	Install drainage in front of 12th tee to reduce ponding in this area.  September - Install drainage around 13th green and apron area to connect with open ditches.	January fit new Grippers to sleeper steps on 2 holes. March continue to stone wet and muddy parts of buggy paths at the 6th and 7th	Clear the hedge at the back of the 4th Tee. Construct temporary fence.  Clear out copse by 6th tee	Continue work as per the tree development plan  Fell selected Leylandii trees as suggested in tree plan and replant with suitable stock  Remove popular roots short of 12th green
<b>2023/24</b>  <b>Review Dates</b> <b>Mar 2023</b> <b>June 2023</b> <b>Sept 2023</b> <b>Dec 2023</b>	Rebuild 18th Tee to same specification as the others. With drainage etc. Monitor and continue rotten sleeper replacement on 3 holes.	Mole Plough. Aeration. Raise and level sunken drains and holes	Continue work on greenside bunkers as per Bunker development plan. (Minimum two bunkers)	Drain old chipping green	Continue green control box renewal 4 holes.  Raise and level green and approach sprinklers on remaining 9 holes.	Install drainage around 15th tee area.  September - Excavate drainage ditch alongside hedge from 13th Apron to 11th Fairway.	January fit new Grippers to sleeper steps on 2 holes. Plan and start buggy paths 14 to 18.  Re Tarmac path at 1st tee and 5th tee	Cut out brambles and undergrowth from woodland behind 16th green.	Continue work as per the tree development plan  Fell selected Leylandii trees as suggested in tree plan and replant with suitable stock.  Fell diseased elms on boundary at 1st and 2nd
<b>2024/25</b>  <b>Review Dates</b> <b>Mar 2024</b> <b>June 2024</b> <b>Sept 2024</b> <b>Dec 2024</b>	Replace sleeper edge on 1st tee and rotten sleeper edges on two more holes.	Mole Plough. Aeration. Raise and level sunken drains and holes	Continue work on greenside bunkers as per Bunker development plan. (Minimum two bunkers)	Plan for the reconstruction of the 1st green.	Continue green control box renewal on 4 holes.  Install approach sprinklers at the 8th.	Install pipe drainage and re-contour front of 7th green approach to divert surface water flooding to green.	Relay right hand path in the 16th valley and extend past the wet area at the top. Continue Buggy Paths 14 to 18  Widen and lengthen path by 16th Tee.	Cut back encroaching scrub right hand side of 7th Green.  Tidy/replace/repair fence to left of 17th tee.	Continue work as per the tree development plan  Fell selected Leylandii trees as suggested in tree plan and replant with suitable stock.  Fell diseased elms on boundary at 1st and 2nd
<b>2025/26</b>  <b>Review Dates</b> <b>Mar 2025</b> <b>June 2025</b> <b>Sept 2025</b> <b>Dec 2025</b>	Re-build ladies 18th tee to same spec as other tees. Replace rotten sleepers on steps and winter tee at 10th.	Mole Plough. Aeration. Raise and level sunken drains and holes	Continue work on greenside bunkers as per Bunker development plan. (Minimum two bunkers)	Reconstruct 1st Green.	Continue green control box renewal on remaining 2 holes.  Audit irrigation system for future repair and improvement.	Plan and Improve practice range drainage.	Continue Buggy Paths 14 to 18.  Replace steps at 5th tee  Re Tarmac path alongside 18th green	Clear copse left of 18th tee.	Continue work as per the tree development plan  Fell selected Leylandii trees as suggested in tree plan and replant with suitable stock.  Fell diseased elms on boundary at 1st and 2nd